## The Republic of the Union of Myanmar Ministry of Construction Department of Highways

## Construction Project Management in DOH, MOC

**Course - Construction Project Management** 

**Prof. Chunho Yeom** 

Presenter
Soe Hlaing Tun
Assistant Director (Civil)
DOH, MOC
MIPD3, ISUS, UoS

### **Qutline**

- **Component of Construction Management**
- **Construction Management System** 
  - I. Planning and Design
    - A. Feasibility Study (FS)
    - B. Detail Design (DD)
  - II. Procurement of Contractor
  - III. Construction Supervision
    - A. Construction Management
    - B. Quality Assurance
    - C. Inspection
  - IV. Completion and Taking Over
  - V. On going Project (MOC & NEDA)

Source: CONSTRUCTION MANAGEMENT GUIDELINE FOR ROAD & BRIDGE (1st Edition) MOC, Myanmar

### Component of Construction

#### Construction Management



## **Construction Management System**



## I. Planning and Design

## I. Planning and Design

- A. Feasibility Study (FS)
- B. Detail Design (DD)

## A. Feasibility Study (FS)

- a) Traffic Study
- b) Fundamental Investigation
- c) Engineering Study
- d) Project Cost Estimate
- e) Preliminary Environmental And Social Consideration

## a) Traffic Study

- \* General Traffic Environment of Myanmar
- \* Traffic Condition
- \* Development Plan
- \* Estimation of Future Traffic Volume

## b) Fundamental Investigation

- Road Investigation
  - Topography
  - Road survey
    - Present status of the existing road
    - Horizontal alignment
    - Vertical alignment
    - Cross section
  - Hydraulic and Hydrological Survey
  - Existing Drainage Facilities
  - Existing Pavement
  - Miscellaneous Facilities
- Existing Bridge Survey
- Geologic And Geological Investigation

## c) Engineering Study Road Design Criteria Classification of Roads Design Speed Geometric Design Criteria **Cross Section** Alignment Design Selection of Routes **Intersection Planning**

- Earth Work Design
- Drainage Design
- Pavement Design
- Bridge Design

Miscellaneous Facility Design

## d) Project Cost Estimate

- > Assumptions For Cost Estimates
- Applied Unit Cost
- Construction Quantities
- Project and Indirect Project Cost Estimate
- Total Project Cost
- Project Cost Comparison of Alternative Routes

## e) Preliminary Environmental And Social Consideration

Present Environmental Status

- Impact Factors Effecting On Environment
- Environmental Impact Review And Mitigation
- Resettlement Plan


## B. Detailed Design (DD)

- a) Alignment Selection
- b) Geometric Design
- c) Pavement Design
- d) Bridge Design
- e) Earth Work Design
- f) Drainage Design

## II. Procurement of Contractor

## Procurement of Contractor

Major Item	Details				
	Advertisement for Bid				
Bidding	Bid Bond				
	Bidding Procedure				
	Bid Form				
	Bid Evaluation				
Quality Inspection for Contractor Work					
Delay Damages					
Payment Method					
Penalty					




#### **Tendering Committee**

- 1/ Tender Committee 2/ Quotation price calculation committee
- 3/ Tender acceptation and evaluation committee
- 4/ Quality inspection and acceptance committee

### **International Practice**

The construction contract of International Federation of Consulting Engineers(FIDIC) has been adopted as standard contract document for building and engineering works designed by employer or by his representative for international contracts



## III. Construction Supervision

## III. Construction Supervision

- A.Construction Management
- B. Quality Assurance
- C.Inspection

## A. Construction Management

- Study of Design Report
- Pre-Construction Survey
- Joint Site Inspection (Consultant + MOC + Contractor)
- Pre-construction Meeting
- Progress Management
- Cost Management
- Safety Management
- \* Environmental Management
- Recording and Reporting

## B. Quality Assurance

- a) Quality Control Plan
- b) Quality Control Specification and Guides
- c) Quality Control Activities

## C. Inspection

- Materials Quality Control
- Workmanship
- Alignment and Dimensions
- Quality Measurement
- Work Progress Monitoring

## IV. Completion and Taking Over

## IV. Completion and Taking Over


- Final Inspection
- Remedy
- Taking over certificates
- Release of Performance Security
- Completion Certificate
  - Completion Reports
  - As-build Drawing
  - Photographs at final inspection
  - Other construction record
  - Design report
  - Topographic data and geological data

# V. On going Project (MOC & NEDA)

## On going Project (MOC & NEDA)









#### PART 1: ACTIVITIES AND COORDINATION



PART 2: THE SUMMARY OF PROGRESS




PART 3: ENVIRONMENT STUDY



PART 4: ENGINEERING STUDY

## PART 1: ACTIVITIES AND COORDINATION

### PROJECT STEERING COMMITTEE (PSC)





















#### COMPLETED THE 1st PUBLIC RELATION-PUBLIC PARTICIPATION ON 17 MAY, 2019
























## PART 2: THE SUMMARY OF PROGRESS




### **COST ESTIMATION**

Item	Description	Amount	factor F	Amount	Provisional Sum
Na		Excenter F(Balt)	)	Incfactor F(Baht)	(Bahr)
1	GENERAL IROMSIONS	29,342,000.00	_	29,342,000.00	0.00
2	EARTHWORKS	1,615,629,890.00	1.1729	1,894,972,297.98	-
3	PAVEMENT	265,563,090.00	1.1729	311,478,948.26	-
4	DRAINAGE	64,795,730.00	1.1729	75,998,911.72	-
5	SIRUCIURES	252,906,220.00	1.1441	289,350,006.30	-
6	MSCELLANEOUS	336,205,820.00	1.1729	394,335,80628	0.00
7	PARTICULAR SPECIFICATIONS	18,510,500.00	1.1729	21,710,965.45	-
	TOTAL	2,582,953,25000		3,017,188,935.99	0.00
	GRANTOTAL			3,017,188,935,99	

<sup>\*\*\*</sup> THE COST INCREASED AROUND 3300 TO 3500 MILLION TH.BAHT, IN FINAL BECAUSE UPGRADED DESIGN AND VALUE SPECIAL PROVISIONAL SUM AND ETC. \*\*\*

## **TENDER DOCUMENTS PREPARATION**





# TENDER DOCUMENTS PREPARATION

No.	Topic					
1	Pre-Qualification: PQ					
2	Form of Tender					
3	Instruction to Tenderers					
4	General and Particular Conditions of Contract					
5	Detailed Construction Specification					
6	Contract Drawing					
7	Equipment and Material Specification					
8	Bill of Quantities					
9	Cost Breakdown					
10	Term of Reference: TOR					
	*** The details in Tender & Bidding Document Report					

# PART 3: ENVIRONMENT STUDY




Figure 8.4-1 Common Environmental Consideration Process

## **ALL MITIGATION MEASURES FOR THE PROJECT**

	2018EIA	2019EIA (Additional )				
<b>Environmental Moni</b>	ronmental Mitigation I itoring Program : 16 Environmental and	4. Additional Mitigation Measure  General Mitigation (2)				
Air Quality (17)	Biodiversity (22) • Tree Species Transplanting	Solid Waste (13)	Construction Phase :			
Noise (5)	activity (2)  Tree Clearing Activity (8)  Forest monitoring Activity	Hazardous Waste (11)	No additional mitigations			
Vibration (5)	(2) • Hunting Controland Other Measures for Wildlife Protection (4) • Deforestation Control Activity (6)	Occupational Health (24)	<ul> <li>Operation Phase: Biological Resource as</li> <li>Forest Rehabilitation Activities (4)</li> <li>Biodiversity Monitoring Activities (3)</li> </ul>			
Surface Water Quality (7)		Chance find (6)	Wildlife Corridor Construction (2)			
Aquatic Ecology (2)		Compensation and Livelihood Restoration (7)				
Soil Erosion (5) and Soil Contaminant (2)		Land Use (3)				
Transportation (11)		Socio-Economic (6)				
Water Use (3)						

# PROJECT AMENDMENTS TO REDUCETO CUTTHE FOREST (POSITIVE IMPACT)








Survey and Detailed De






#### **WILDLIFE CORRIDORS DESIGN**

- 1. 10 Bridges for Wildlife
- 2. 2 Box culvert : sta. 100+375 and sta.126+373 for Wildlife
- 3. Wildlife crossing with Mesh Fence as a barriers and approach line from both sides of Box Culvert Bridge



1. WILDLIFE CORRIDORS
RC. CONCRETE BOX CULVERT



# PART 4: ENGINEERING STUDY

## **Traffic Survey**




Figure 5.1-1 Mid-block Survey Points, Turning Movement Survey Points and Origin-Destination Survey Point

#### TRAFFIC SURVEY ON 25 MARCH TO 28 MARCH 2019 AT DAWE!



# Soil & Geology Investigation



#### COMPLETED THE SOIL AND GEOLOGY INVESTIGATION ON 4-6 JUNE, 2019













#### **CONDUCT THE MATERIAL INVESTIGATION**

- The consultant surveys the locations of material and found that are Cover in the previous report.
- Recheck 5 Main Material Resources

No.	Description	Sta.	Coordinate (UTM: 47 P)		
		19	N	E	
1	Sand (S-1) Laterite (L-1)	22+200	1579761.64	416854.36	
2	Rock (R-0)	24+900	1578478.15	418379.39	
3	Crushed Rock (R-1)	42+850	1576829.98	429381.36	
4	Laterite (L-2)	102+400	1564843.13	472581.83	
5	Crushed Rock (R-2)	145+300	1539598.38	500705.00	





# Topographic Surveying and Leveling

- ✓ Unmanned Aerial Vehicle (UAV) is completed for Aerial Photograph to create Base Map
- ✓ Between 29 April 3 May 2019 by attaching the camera to the UAV
- Taking a vertical image for at least 60 percent overlapping
- which will provide the most detailed and current information
- After that, the picture was taken together as an aerial photo map to create Base Map





No	Contents	Previous Study	This Study
1	GPS Control Points	61 GPS Primary Control Points (permanent)	Reviewed and No Revision
2	Traverse	102 Traverse Monument (permanent)	Reviewed and No Revision
3	Primary Vertical Control Points (BM)	Completed	Reviewed and No Revision
4	Right of Way	40 m	70 m (Refer to Comment of Committee of Inception report 4th May 2019)
5	Topographic Map	Ground Survey	Conducted by UAV (29 April - 3 May 2019)



### Pavement Structure Design

No	Types of Pavement	Location	Distance
1	Asphaltic concrete pavement	Almost along the route	≈ 116 KM.
2	Concrete pavement	The steep slope, rest area, Toll Plaza and the Intersection	≈ 24 KM.





RIGHT OF WAY PLAN 70.00 M.



# **DESIGN OF 19 BRIDGES**

Nb	Station .	Total Width	Nb. of	Span Arrangement	Total Length	9.bstructure	Upper Structure	
		(m)	Span	фаннацыя	(m)		slab	beam
1	16+685.787	11.00	7	(1x32.25)+(5x35.00)+(1x32.25)	239.50	Reinforced Concrete	Reinforced Concrete	Prestressed l-Girder
2	19+271.168	11.00	5	(1)29,65]+(3)30,00]+(1)29,65]	149.30	Reinforced Concrete	Reinforced Concrete	Prestressed l-Girder
3	21+933,446	11.00	5	(1)29,65]+(3)30,00]+(1)29,65]	149.30	Reinforced Concrete	Reinforced Concrete	Prestressed l-Girder
4	22+660.669	11.00	3	(1x14.70)+(1x15.00)+(1x14.70)	44.40	Reinforced Concrete	Reinforced Concrete	Prestressed l-Girder
5	45 <del>19</del> 04.237	11.00	3	(1x14.70)+(1x15.00)+(1x14.70)	44.40	Reinforced Concrete	Reinforced Concrete	Prestressed l-Girder
6	49+159.614	11.00	3	(1x14.70)+(1x15.00)+(1x14.70)	44.40	Reinforced Concrete	Reinforced Concrete	Prestressed l-Girden
7	6 <del>61</del> 397.180	11.00	4	(1x14.70)+(2x15.00)+(1x14.70)	59.40	Reinforced Concrete	Reinforced Concrete	Prestressed l-Girder
8	69+596,000	11.00	5	(1)29,65]+(3)30,00]+(1)29,65]	149.30	Reinforced Concrete	Reinforced Concrete	Prestressed l-Girder
9	72 <del>19</del> 14.808	11.00	1	(1x15.00)	15.00	Reinforced Concrete	Reinforced Concrete	Prestressed l-Girder
10	76+512.788	11.00	3	(3x15.00)	45.00	Reinforced Concrete	Reinforced Concrete	Prestressed l-Girder
11	77+175.806	11.00	3	(3x15.00)	45.00	Reinforced Concrete	Reinforced Concrete	Prestressed l-Girder
12	81+454.206	11.00	3	(3x15.00)	45.00	Reinforced Concrete	Reinforced Concrete	Prestressed l-Girder
13	90+901.487	11.00	3	(3x15.00)	45.00	Reinforced Concrete	Reinforced Concrete	Prestressed l-Girder
14	106+956,450	11.00	3	(3x15.00)	45.00	Reinforced Concrete	Reinforced Concrete	Prestressed l-Girder
15	107+951.157	11.00	1	(1x15.00)	15.00	Reinforced Concrete	Reinforced Concrete	Prestressed l-Girder
16	120+248.408	11.00	1	(1x15.00)	15.00	Reinforced Concrete	Reinforced Concrete	Prestressed l-Girder
17	140+081.438	11.00	1	(1x15.00)	15.00	Reinforced Concrete	Reinforced Concrete	Prestressed l-Girder
18	150+591,392	11.00	1	(1x15.00)	15.00	Reinforced Concrete	Reinforced Concrete	Prestressed l-Girder
19	154+755.965	11.00	1	(1x15.00)	15.00	Reinforced Concrete	Reinforced Concrete	Prestressed l-Girden



#### CONCLUDE ROAD LIGHTING AND TRAFFIC SIGNALS

No.	Contents	Remark
1	Marking	Along Route and Intersection
2	Road Lighting	Intersection (STA. 18 + 500 / STA. 54 + 354 / STA. 68 + 400) And Toll Booth
3	Flashing Yellow Light (Solar Cell)	Intersection (STA. 18 + 500 / STA. 54 + 354 /STA. 68 + 400) And Traffic Change Over












#### **SAFETY DEVICES**







#### **CONSIDER THE LOCATION OF TOLL PLAZA AND REST AREA** Pagawyun STA.18+918 : TOLL PLAZA 1 STA. 78+750 : REST AREA **DSEZ Project Site TOLL PLAZA 1** STA.155+700:TOLL PLAZA 2 Begining of Contract 2 STA. 68+393 **Begining of Contract 1** STA. 16+458 Myitto Myitta **REST AREA** ANDAMAN Dawei **Ending of Contract 1** SEA **Ending of Contract 2** Laungion ecodini STA. 156+500 Phu Nam Ron **TOLL PLAZA 2** hayetchaung Yebyu Contract 1 Contract 2 Section 2 Section 1 Section 3 espération

# TOLL PLAZA PLAN & KEY MAP

